



Submittal General Notes

- ◆ REFER TO THE BENCHMARK HMF COMMERCIAL ARCHITECTURAL GUIDE FOR SPECIFICATIONS AND MANUFACTURING LIMITATIONS ON SPECIFIC PRODUCT TYPES.
- ◆ MATERIAL ILLUSTRATED IN THIS SUBMITTAL PACKAGE WILL BE FABRICATED ONLY AFTER FORMAL APPROVAL BY THE ARCHITECT, RECEIPT OF APPROVAL FOR THE HARDWARE SCHEDULE AND ALL REQUIRED HARDWARE TEMPLATES.
- ◆ ALL DOORS AND FRAMES WILL BE CHEMICALLY WASHED AND DRIED BEFORE RECEIVING ONE COAT OF PRIME PAINT.
- ◆ ALL DOORS AND FRAMES WILL BE PROPERLY REINFORCED FOR SURFACE MOUNTED HARDWARE AS SPECIFIED. DRILLING AND TAPPING FOR SURFACE MOUNTED HARDWARE TO BE DONE IN FIELD BY OTHERS.
- ◆ FUNCTION HOLES FOR LOCK SETS AND EXIT DEVICES WILL BE PROVIDED AT FACTORY. ANY MOUNTING HOLES WILL BE DRILLED AND/OR TAPPED IN FIELD BY OTHERS.
- ◆ ALL FRAMES WILL BE SUPPLIED WITH WALL AND FLOOR ANCHORS AS SPECIFIED ON SCHEDULE.
- ◆ FIELD WELDING, GRINDING, FINISHING & ATTACHMENT OF FIELD SPLICES TO BE DONE IN FIELD BY OTHERS.
- ◆ ALL STANDARD TYPE HARDWARE WILL BE LOCATED AT THE SPECIFIED MANUFACTURES LOCATIONS. NON STANDARD HARDWARE MUST HAVE SPECIFIED LOCATIONS. HARDWARE ITEMS SUCH AS RIM EXIT PANIC DEVICES AND VERTICAL ROD EXIT DEVICES WILL BE LOCATED AT MANUFACTURES SUGGESTED LOCATION UNLESS OTHERWISE SPECIFIED.
- ◆ INSTALLATION OF GLASS AND GLAZING TO BE DONE IN FIELD BY OTHERS.
- ◆ WHEN HOLLOW METAL DOORS OR FRAMES ARE USED IN CONJUNCTION WITH ALUMINUM, STRUCTURAL STEEL, AND/OR WOOD PRODUCTS, COORDINATION OF HARDWARE LOCATIONS WILL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
- ◆ ALL FRAMES IN MASONRY CONSTRUCTION ARE TO BE FILLED WITH GROUT WHERE PRACTICAL. IF ADDITIVES ARE USED IN MORTAR TO DECREASE SETTING TIME, A BITUMINOUS COATING SHOULD BE APPLIED TO THE INSIDE OF THE JAMBS BY THE GENERAL CONTRACTOR.

JOB:
BUILDING:
CONTRACTOR:
CONTRACT #:
WRITTEN UP BY:
DATE: