

(Toll Free) Phone 866-452-1845

Fax 910-452-1848

Steel Stiffened Core - Butted Edge Construction

		ĺ
Butted Edge Seam Construction		1
22 Ga Stiffeners at 6" CL Maximum		
Fiberglass Insulation		
14 Gauge Full Height Continuous Hinge -		
& Lock Channel Rein.		
14 Gauge Top and Bottom Channels		
Hardware Reinforcement:		
Hinge = 7 Gauge		
161 Lock = 16 Gauge		
86 Lock = 14 Gauge		
Closer = 14 Gauge		
Baked on Grey Primer		
Square or Bevelled Edge		
Seamless - Fully Welded or Tack & Fill		
Fire Ratings:		
Thickness 1 3/4" - 3 1/4" Fire Rated		
1 3/8" Available Non Rated		
Available 18, 16, & 14 Gauge - Rated		
Available 12 Gauge Non Rated		
90 Min. to 5-0 x 12-0 (10-0 x 12-0 Pr)		
3 Hr. to 4-0 x 8-0 (8-0 x 8-0 Pr)		
Estimated Performance:		
Acoustical Value - STC 24	μ	
R Value - 1.17		
U Value855		
	L	_